

405 State Highway 121 (Bypass) Building C, Suite 100 Lewisville, TX 75067 Telephone: 972-315-3922 Fax: 972-315-5181

Fax: 972-315-5181 www.eaest.com

29 September 2020

Ms. Raji Josiam Remedial Project Manager U.S. Environmental Protection Agency (EPA) Region 6 1201 Elm Street, Suite 500, SEDRA Dallas, Texas 75270-2102

RE: Annual Technical Memorandum on the Soil Vapor Extraction System Operation and

Maintenance July 2019 to July 2020, Revision 00 Jones Road Ground Water Plume Superfund Site Remedial Action

EPA Region 6 Remedial Action Contract 2

Contract: EP-W-06-004

Task Order: 0129-RARA-06NK

Dear Ms. Josiam:

EA Engineering, Science, and Technology, Inc., PBC is submitting the Annual Technical Memorandum on the Soil Vapor Extraction System Operation and Maintenance July 2019 to July 2020, Revision 00 for the above-referenced Task Order on this day. The deliverable will be transmitted to the project SharePoint Site for download.

If you have any questions regarding this submittal, please call me at (972) 315-3922.

Sincerely,

Patrick Appel, PMP Project Manager

cc: William G. Johnson Jr., EPA Project Officer Patrick Appel, EA Project Manager Tim Startz, EA Program Manager (letter only via e-mail) Diane Britt, TCEQ Remedial Project Manager File

| TRANSMITTAL | OF DOCUMENTS FOR ACCEPTANCE BY EPA | | DATE: 29 September 2020 | TRANSMITTAL NO.: 0015 | | | |
|--|--|---------------|---|-----------------------|--|--|--|
| TO: | | FROM: | | | | | |
| Ms. Raji Josiam U.S. Environmental Protection Agency Region 6 | | | Patrick Appel EA Engineering, Science, and Technology, Inc., PBC | | | | |
| SUBTASK NO. | DELIVERABLE | NO. OF COPIES | | | | | |
| 10.5 | Annual TM on the SVE Systm O&M, Revision 00 Jones Road Ground Water Plume Superfund Site Remedial Action | | EPA: Electronic Copy via Email TCEQ: Electronic Copy via Email, 1 Compact Disc, 1 Hard Copy | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | ACCEPTAN | CE ACTIO | N | | | | |
| DOCUMENTS FOUND ACCEPTABLE (LIST BY SUBTASK NO.) | | | NAME/TITLE/SIGNATURE OF REVIEWER DATE | | | | |



Annual Technical Memorandum on the Soil Vapor Extraction System Operation and Maintenance July 2019 to July 2020

Jones Road Ground Water Plume Superfund Site Remedial Action Houston, Harris County, Texas EPA Identification No. TXN000605460

EPA Region 6 Remedial Action Contract 2 Contract No.: EP-W-06-004 Task Order No.: 0129-RARA-06NK

Prepared for

U.S. Environmental Protection Agency Region 6 1201 Elm Street, Suite 500 Dallas, Texas 75270-2102

Prepared by

EA Engineering, Science, and Technology, Inc., PBC 405 State Highway 121 (Bypass)
Building C, Suite 100
Lewisville, Texas 75067
(972) 315-3922

September 2020 Revision: 00 EA Project No. 14342.129

CONTENTS

| | | | <u>Page</u> |
|------|------------|---|-------------|
| LIST | Γ OF FIC | GURES | ii |
| LIST | Γ OF TA | BLES | iii |
| LIST | Γ OF AP | PENDIXES | iv |
| LIST | Γ OF AC | RONYMS AND ABBREVIATIONS | v |
| 1. | INTR | ODUCTION | 1 |
| 2. | BAC | KGROUND | 1 |
| 3. | SOIL | VAPOR EXTRACTION TREATMENT SYSTEM | 2 |
| | 3.1 3.2 | SYSTEM COMPONENTS NORMAL OPERATING AND MAINTENANCE PROCEDURES | |
| | 3.3 | REPAIRS AND ADJUSTMENTS | 4 |
| | | 3.3.1 Shallow Moisture Separator Transfer Pump | |
| | | 3.3.2 Fine Bubble Aerator | |
| | | 3.3.3 Shallow System Vapor-Phase GAC Vessels | 3 |
| 4. | SYST | TEM PERFORMANCE | 5 |
| | 4.1 | SYSTEM READINGS | 5 |
| | 4.2 | AIR SAMPLING RESULTS | |
| | 4.3 | PHOTOIONIZATION DETECTOR MEASUREMENTS | 7 |
| | 4.4 | SVE WATER TREATMENT SYSTEM SAMPLING RESULTS | 7 |
| | 4.5 | GROUNDWATER SAMPLING RESULTS | 7 |
| 5. | SUM | MARY AND CONCLUSIONS | 8 |
| 6 | REFE | FRENCES | 10 |

LIST OF FIGURES

| <u>Number</u> | Title |
|---------------|--|
| 1 | Soil Vapor Extraction Well Locations |
| 2 | Piping and Instrumentation Diagram of Soil Vapor Extraction System |
| 3 | Tetrachloroethene Results for Deep Soil Vapor Extraction Wells |
| 4 | Trichloroethene Results for Deep Soil Vapor Extraction Wells |
| 5 | Tetrachloroethene Results for Shallow Soil Vapor Extraction Wells |
| 6 | Trichloroethene Results for Shallow Soil Vapor Extraction Wells |
| 7 | PCE and TCE Concentrations, Deep SVE System Influent |
| 8 | Contaminant Mass Removal, Deep SVE System |
| 9 | PCE and TCE Concentrations, Shallow SVE System Influent |
| 10 | Contaminant Mass Removal, Shallow SVE System |
| 11 | Deep SVE System PID Readings, Total VOC |
| 12 | Shallow SVE System PID Readings, Total VOC |
| 13 | Water Treatment System Analytical Sampling Results |
| 14 | Concentration of PCE in Ground Water, Deep SVE Wells |

LIST OF TABLES

| <u>Number</u> | <u>Title</u> |
|---------------|---|
| 1 | SVE System Readings |
| 2 | Deep SVE System Analytical Sampling Results |
| 3 | Deep SVE System Analytical Sampling Results Summary |
| 4 | Deep SVE System Uptime and Mass Removal Summary |
| 5 | Deep SVE Well Analytical Sampling Results |
| 6 | Shallow SVE System Analytical Sampling Results |
| 7 | Shallow SVE System Analytical Sampling Summary |
| 8 | Shallow SVE System Uptime and Mass Removal Summary |
| 9 | Shallow SVE Well Analytical Sampling Results |
| 10 | Deep SVE System Photoionization Detector Readings |
| 11 | Shallow SVE System Photoionization Detector Readings |
| 12 | Water Treatment System Sampling Results |
| 13 | Summary of Water Treatment System Analytical Sampling |
| 14 | Summary of Ground Water Analytical Sampling |

EA Project No.: 14342.129

Revision: 00

Page iv September 2020

EA Engineering, Science, and Technology, Inc., PBC

LIST OF APPENDIXES

| <u>Appendix</u> | <u>Title</u> |
|-----------------|---|
| A | System Readings Datasheets (Provided via CD) |
| В | Field Logbook (Provided via CD) |
| C | Air Sampling Analytical Reports (Provided via CD) |
| D | Water Sampling Analytical Reports (Provided via CD) |

EA Project No.: 14342.129

Revision: 00

Page v

September 2020

LIST OF ACRONYMS AND ABBREVIATIONS

bgs below ground surface

COC Contaminant of concern

DCE Dichloroethene

EA Engineering, Science, and Technology, Inc., PBC

EPA U.S. Environmental Protection Agency

ft. Foot (feet)

GAC Granular activated carbon

in. wc Inches of water column in. Hg Inches of mercury

lb Pound(s)

MCL Maximum contaminant level

μg/L Microgram(s) per liter

μg/m³ Microgram(s) per cubic meter

O&M Operation and maintenance

% Percent

PCE Tetrachloroethene

PID Photoionization detector

PLC Programmable logic controller

scfm Standard cubic feet per minute

site Jones Road Groundwater Plume Superfund Site

SVE Soil vapor extraction

TCE Trichloroethene

VC Vinyl chloride

VOC Volatile organic compound

1. INTRODUCTION

EA Engineering Science and Technology, Inc., PBC (EA) has prepared the Annual Technical Memorandum on the Soil Vapor Extraction (SVE) System Operation and Maintenance (O&M), July 2019 to July 2020 for Task Order No. 0126-RARA-06NK under U.S. Environmental Protection Agency (EPA) Response Action Contract EP-W-06-004.

This memorandum covers the period of 30 July 2019 through 31 July 2020. EA has operated and maintained the SVE system at the Jones Road Ground Water Plume Superfund Site (site) since the system startup on 24 July 2019. This memorandum discusses the O&M activities, sampling results, and performance of the SVE treatment system.

2. BACKGROUND

The site is located in the northwest portion of Houston, Harris County, Texas at 11600 Jones Road. The contaminants of concern (COCs) include tetrachloroethene (PCE) and related daughter products trichloroethene (TCE), cis-1,2-dichloroethene (DCE), trans-1,2-DCE, and vinyl chloride (VC), which are present in the subsurface aguifers and vadose zones.

The most significant aquifers at the site are the Evangeline Aquifer and the Chicot Aquifer. The Chicot Aguifer is estimated to extend to a depth of approximately 400 feet (ft) below ground surface (bgs). The first water-bearing unit exists from approximately 20 to 35 ft bgs, where soils consist of interbedded sand, silt, and silty clay. The Shallow SVE System (SS) is intended to treat Shallow Source Area Soil, which exists in the unsaturated zone above 20 ft bgs where soils consist of high-plasticity clay.

The second water-bearing unit is present at a depth of approximately 110 ft bgs and is considered to be the first major water-bearing unit of the Chicot Aquifer. A well-developed sand zone exists from approximately 60 to 110 ft bgs, a clay zone with minor sand lenses that exists from approximately 110 to 150 ft bgs, a sand unit underlies the clay and extends from approximately 150 to 190 ft bgs. The Deep SVE System is intended to target the Deep Unsaturated Chicot Sand, which exists from 60 to 110 ft bgs. Stratigraphy across the site is known to be highly variable.

3. SOIL VAPOR EXTRACTION TREATMENT SYSTEM

This section describes SVE system components, SVE system O&M, and system repairs and adjustments.

3.1 SYSTEM COMPONENTS

Two SVE systems (deep and shallow) are present at the site to address contamination in different subsurface zones. Each SVE system consists of SVE wells, a conveyance piping network and influent manifold, a moisture separator, SVE pumps, and vapor-phase granular activated carbon (GAC) treatment vessels. The deep SVE is driven by a Rotron blower and the shallow SVE system is driven by a Travaini liquid ring pump. Detailed descriptions of the SVE system components are available in the Soil Vapor Extraction System Operation and Maintenance Manual (EA 2020). The SVE wells are positioned across the site as shown in Figure 1.

Water captured by either moisture separator is transferred into the water treatment system, which consists of two transfer pumps that move water out of the moisture separators, two bag filters, one Organoclay treatment vessel, two liquid-phase GAC treatment vessels, a 2,000-gallon storage tank, a transfer pump to move water out of the storage tank, and two subsurface injection wells for disposal of treated water. A fine bubble aerator was retrofitted in the storage tank to provide additional water treatment capacity, as described in Section 3.3.2.

A piping and instrumentation diagram of the SVE system is provided in Figure 2. The pumps and other components of the system are able to be monitored and controlled via a central programmable logic controller (PLC) located at the site.

3.2 NORMAL OPERATING AND MAINTENANCE PROCEDURES

The SVE system has been operating since July 2019. Scheduled O&M visits include the following activities, including sampling, as outlined in the SVE System Operation and Maintenance Manual:

Weekly

- Record the pressure or vacuum readings at the following locations:
 - o (2) SVE pump influent (manifold header), Deep and Shallow
 - o (2) SVE pump effluent, Deep and Shallow
 - o (2) 1st GAC influent, Deep and Shallow
 - o (2) 1st GAC effluent / 2nd GAC influent, Deep and Shallow
 - o (2) 2nd GAC effluent (pre-atmospheric discharge), Deep and Shallow.
- Record photoionization detector (PID) readings at the following locations:
 - o (10) Piping manifold well legs (raw well air), Deep

- o (11) Piping manifold well legs (raw well air), Shallow
- o (2) 1st GAC influent (pre-treatment), Deep and Shallow
- o (2) 1st GAC effluent (mid-treatment), Deep and Shallow
- o (2) 2nd GAC effluent (post-treatment), Deep and Shallow.
- (21) Record the rotameter reading on each leg of the SVE manifold, Deep and Shallow.
- Check manifold legs on the shallow SVE system for excessive water intake.
- (2) Record the system total flow rate from the PLC, Deep and Shallow.
- (2) Record the SVE pump effluent temperature, Deep and Shallow.
- Record fluid level in the storage tank.
- Check the level and top off, if necessary: sealant oil in the liquid ring pump (shallow SVE system).
- Replace bag filters.
- Inspect the air lines and fittings supplying the water storage tank aerator.
- Inspect the air compressor for excessive noise or vibration.
- Inspect for water in the air compressor tank and check operation of the automatic tank drain device.
- Open or close the control valves for the storage tank discharge, based on current seasonal water inflow rate to the system and current tank level.
- Audibly inspect SVE and water transfer pumps for excessive noise or vibration during operation.
- Visually inspect treatment vessels (vapor and liquid), valves, and adjacent piping for leaks.
- Visually inspect piping manifolds for damage or air leaks.
- Visually inspect all system components.

Monthly

Perform all weekly O&M tasks

- Collect vacuum readings at each SVE wellhead
- Collect the vapor samples listed below and submit them for laboratory analysis:
 - o (2) 1st GAC influent (pre-treatment), Deep and Shallow
 - o (2) 1st GAC effluent (mid-treatment), Deep and Shallow
 - o (2) 2nd GAC effluent (post treatment), Deep and Shallow.
- Perform pump-specific O&M tasks, such as applying grease at manufacturer-specified intervals.
- Check exhaust fans and vent louvers.
- Inspect perimeter fence and entry gates for damage or security concerns.
- Download system performance logs from the remote access website:
 - o Component run time data
 - Analog data
 - o Flow meter totalizer data
 - o Discrete data.

3.3 REPAIRS AND ADJUSTMENTS

Repairs and adjustment made to the shallow SVE system during the operational period are described here.

3.3.1 Shallow Moisture Separator Transfer Pump

The moisture separator transfer pump was damaged due to the fine sediment entrained in the separated water. Repair of the pump included replacing some pump components and was carried out by the pump manufacturer's local authorized service company. To prevent additional damage caused by the sediment, a gearbox was retrofitted to the pump to reduce the rotational speed of the pump by a 5:1 ratio. During the repair, sediment was discovered in the downstream piping and water storage tank. The liquid-phase GAC and Organoclay were changed out on 12 November 2019, at which time sediment was discovered within the Organoclay and GAC vessels. From startup, the bag filter housings had been fitted with 5-micron filter bags, which proved ineffective in capturing a significant portion of the sediment entrained in the water. Beginning November 2019, 1-micron filter bags were used but they still did not capture a significant portion of the sediment before passing through the rest of the water treatment system.

3.3.2 Fine Bubble Aerator

EA stopped discharging treated water effluent to the injection wells when effluent water samples showed elevated levels of PCE during startup testing on 30 July and 1 August 2020. The criteria for disposal via subsurface injection during the system design was considered to be the EPA's Maximum Contaminant Level for PCE in drinking water, which is 5 micrograms per liter (μ g/L).

The elevated effluent concentration was caused by higher than anticipated influent concentration and insufficient treatment of the water by the system. Additional treatment was accomplished via recirculation of the water from the storage tank through the GAC vessels and aeration of the water via a sump pump within the storage tank, which was effective in bringing the PCE concentration below the MCL. Subsequently, sampling was done prior to discharge of treated water from the storage tank to confirm PCE concentration was below the MCL. On 25 February 2020, the sump pump was replaced with a fine bubble aerator to improve the water treatment capacity of the system. The air compressor within the system enclosure was connected to provide a constant stream of air to the aerator. Since the aerator was installed, every storage tank water sample has shown PCE concentrations below the MCL, even though samples from the GAC effluent shows the GAC continues to be ineffective.

3.3.3 Shallow System Vapor-Phase GAC Vessels

Water accumulated in the shallow SVE system vapor-phase GAC vessels, causing a pressure relief valve to be tripped and discharge untreated influent directly to the atmosphere. The water typically was gravity drained during temporary system shutdowns, and put back into the moisture separator to be processed through the water treatment system. On 10 June 2020, GAC particles were observed in the water draining from the vessels. EA subcontractor TetraSolv inspected the vessels on 10 July 2020 and observed damage to the screen that holds the GAC in place. The screen was replaced with a new one and the shallow SVE system was able to be restarted immediately.

The deep SVE system did not require any repairs or adjustments that required downtime.

4. SYSTEM PERFORMANCE

4.1 SYSTEM READINGS

The deep and shallow SVE systems are designed to run continuously (24 hours a day, 7 days a week). The systems were temporarily shut down to conduct O&M, repairs, GAC change outs, site wide ground water and indoor air sampling, and optimization. Weekly routine O&M activities do not require system shutdown. System readings presented in Table 1 and summarized below are for the period from 30 July 2019 to 31 July 2020.

The blower for the deep SVE system operated for 7,980 hours (approximately 90% uptime). The total system flow rate ranged between 227 and 336 standard cubic feet per minute (scfm) and averaged approximately 294 scfm. Vacuum at the pump influent ranged between 32.7 and 66.8 inches of water column (in. WC) and averaged 47.8 in. WC. The blower effluent temperature ranged between 101 and 170 degrees Fahrenheit (°F) and averaged approximately 144 °F.

The liquid ring pump for the shallow SVE system operated for 6,640 hours (approximately 75% uptime). The total system flow rate ranged between 15.8 and 55.4 scfm and averaged approximately 35.9 scfm. Vacuum at the pump influent ranged between 23.1 and 26.7 inches of mercury (in. Hg) and averaged 24.6 in. Hg. The pump effluent temperature ranged between 98 and 133 degrees Fahrenheit (°F) and averaged approximately 117 °F. The shallow SVE system generated 26,465 gallons of water in the moisture separator, which were processed through the water treatment system.

Field documentation, field datasheets, and field logbooks are provided in Appendix A and Appendix B.

4.2 AIR SAMPLING RESULTS

The July 2019 sampling was performed during the system startup period. Other sampling events have occurred during normal system operations. No sampling has occurred after significant periods of system shutdowns.

Deep SVE System

Air samples for the treatment system were collected in Tedlar bags from sampling ports located on the treatment vessels. The deep system samples are collected before, between, and after the two GAC treatment vessels. Table 2 provides a complete listing of sample results for six COCs from the deep SVE system. A summary of PCE and TCE results is provided in Table 3. The influent sample results for the deep SVE system are shown in Figure 7.

As of 31 July 2020, approximately 3,830,000 cubic meters (135,000,000 cubic feet) of air have been extracted by the deep SVE system (Table 4). This volume represents approximately 120 pore volumes. The target pore volume flushing to achieve remediation during the design stage was estimated at 500 pore volumes. However, this was an estimate and actual soil vapor concentrations and mass removal rates should be utilized to determine achieving the remedial objectives. The monthly and cumulative mass removal trends for the deep SVE system are provided in Figure 8.

Air samples for the deep SVE wells were collected in Tedlar bags from sample ports on the influent piping manifold. A diaphragm sampling pump was used to draw air into the bags because the sample ports are under a vacuum while the system is running. The analytical reports for sampling activities are provided in Appendix C. The wellhead sample results for the deep SVE wells are provided in Table 5 and shown in Figure 3 and Figure 4

Shallow SVE System

Air samples for the treatment system were collected in Tedlar bags from sampling ports located on the treatment vessels. The shallow system samples are collected before, between, and after the two GAC treatment vessels. Table 6 provides a complete listing of sample results for six

COCs from the shallow SVE system. A summary of PCE and TCE results is provided in Table 7. The influent sample results for the deep SVE system are shown in Figure 9.

374,000 cubic meters (13,200,000 cubic feet) of air have been extracted by the shallow SVE system (Table 8). This volume represents approximately 390 pore volumes. The target pore volume flushing to achieve remediation during the design stage was estimated at 500 pore volumes. However, this was an estimate and actual soil vapor concentrations and mass removal rates should be utilized to determine the achieving remedial objectives. The monthly and cumulative mass removal trends for the deep SVE system are provided in Figure 10.

Air samples for the shallow SVE wells were collected in Tedlar bags from sample ports on the influent piping manifold. A diaphragm sampling pump was used to draw air into the bags because the sample ports are under a vacuum while the system is running. The analytical reports for sampling activities are provided in Appendix C. The wellhead sample results for the shallow SVE wells are provided in Table 9 and shown in Figure 5 and Figure 6.

4.3 PHOTOIONIZATION DETECTOR MEASUREMENTS

PID readings were collected starting 12 May 2020 from the SVE treatment system and from the manifold for each SVE well. The deep SVE system PID readings are presented in Table 10 and Figure 11. The shallow SVE system PID readings are presented in Table 11 and Figure 12.

4.4 SVE WATER TREATMENT SYSTEM SAMPLING RESULTS

Water samples were collected in volatile organic analysis sample containers from sampling ports located before, between, and after the two GAC treatment vessels and from within the water storage tank. The influent sample is drawn from a sample port before the Organoclay treatment vessel. Water system sampling typically occurs on an as-needed basis during periods of high water capture by the SVE system. During this period, higher water capture occurred during the summer, fall, and spring, with lower water capture during the winter months. Table 12 provides a complete listing of sample results for six COCs from the water treatment system. A summary of PCE and TCE results is provided in Table 13. Sampling trends for the water treatment system are provided in Figure 13.

4.5 GROUNDWATER SAMPLING RESULTS

Groundwater samples were collected using a low-flow procedure from deep and shallow wells during site-wide sampling events in June 2019 (prior to SVE system startup), February 2020, and June 2020. Samples were analyzed for volatile organic compounds (VOC)s by EPA Method 8260B. A summary of the PCE concentrations from the samples are provided in Table 14.

5. SUMMARY AND CONCLUSIONS

During this operation period, the following trends were noted:

- PCE and TCE concentrations at the deep SVE system influent (Pre-GAC) have continuously trended down (Table 3, Figure 7). When comparing startup sampling in July 2019 and the most recent sampling in July 2020, concentrations of all COCs have decreased.
- PCE and TCE mass removal rates from the deep SVE system trended down due primarily to decreasing influent concentrations (Table 4, Figure 8). The monthly PCE and TCE removal rates during August 2019 were 0.06807 pounds per hour (lb./hr.) and 0.00235 lb./hr., respectively. The monthly PCE and TCE removal rates during July 2020 were 0.00001 lb./hr. and 0.00000 lb./hr., respectively.
- PCE and TCE concentrations in every deep SVE well decreased between July 2019 and January 2020 with one exception (Table 5). TCE increased in SVE-2 from 2,500 micrograms per cubic meter (μg/m³) to 2,800 μg/m3. The lowest decrease was observed in SVE-1, which saw a 13% decrease in concentration of PCE and 14% decrease in concentration of TCE. The highest decrease was observed in SVE-4, which had 99% decrease in PCE and TCE concentrations.
- During the reporting period, 68,429 grams (151 pounds) of PCE and 1,945 grams (4.3 pounds) of TCE were extracted from the deep SVE system (Table 4).
- PCE and TCE concentrations at the shallow SVE system influent (Pre-GAC) trended down between October 2019 and April 2020 but trended up between April and July 2020 (Table 6, Figure 9). When comparing startup sampling in July 2019 and the most recent sampling in July 2020, concentrations of all COCs have decreased.
- PCE and TCE mass removal rates from the shallow SVE system trended down between October 2019 and April 2020 but trended up between April and July 2020 (Table 8). This occurred despite lower overall air flow rates in May, June, and July of 2020.
- Between July 2019 and January 2020 concentrations of PCE and TCE fluctuated in every shallow SVE well. Four wells exhibited increased PCE concentrations and seven wells showed decreasing PCE concentrations. Three wells had increased TCE concentrations and eight wells had decreased TCE concentrations.
- During the current period, 62,255 grams (137 pounds) of PCE and 2,956 grams (6.5 pounds) of TCE were extracted from the shallow SVE system (Table 8).
- During the drier winter months, water influent flow rate was significantly decreased, allowing for more consistent uptime of the shallow SVE system and continual decrease in PCE and TCE influent concentrations and mass removal (Table 1, Table 8, Figure 9).

September 2020


Wetter spring weather resulted in more water capture and more system shutdowns due to high water levels and high pump temperature.


- Concentrations of PCE and TCE in the water system influent samples have trended downwards (Table 13, Figure 13).
- In every sampled case, water treatment in the GAC vessels was insufficient in bringing effluent below the MCL for PCE in drinking water, which is 5 μg/L (Table 13). Additional treatment was achieved by mixing water within the storage tank or introducing the fine bubble aerator prior to discharging water via subsurface reinjection.
- PCE was non-detectable in ground water collected from eight of 11 shallow wells sampled in February and June 2020 (Table 14). Only one well exceeded the MCL for PCE in June 2020, which was MW-20 located near the center of the parking lot at the site.
- PCE concentration in ground water collected from deep SVE wells decreased from June 2019 to June 2020 (Table 14). The maximum observed decrease in PCE concentration was 91% at SVE-2. The minimum observed decrease in PCE concentration was 12% at SVE-8. During the June 2020 sampling event, none of the deep SVE wells had concentrations below the MCL for PCE.

Revision: 00 Page 10 of 10 September 2020

6. REFERENCES

EA Engineering, Science, and Technology, Inc., PCB (EA). 2020. Soil Vapor Extraction System Operation and Maintenance Manual, Jones Road Ground Water Plume Superfund Site, Revision 00. August.





Shallow Soil Vapor Extraction Well

Deep Soil Vapor Extraction Well

[_____1

11600 Jones Road

Note:

SVE-08 was installed during the Remedial Investigation for the site. It is not currently connected to the Deep SVE System.

Image Source: GoogleEarth Pro, 20:







Remedial Action
Jones Road Ground Water Plume
Houston, Harris County, Texas

Figure 2
Piping and Instrumentation Diagram of Soil Vapor Extraction System

EA Project No.: 14342.129

Revision: 00





TALES STATES TO THE MAN OR WAS A PROTECTED TO THE PROTECT OF THE P



Remedial Action
Jones Road Ground Water Plume
Houston, Harris County, Texas

TO NAME TO THE PROTECTO



Remedial Action


Jones Road Ground Water Plume

Houston, Harris County, Texas



OMITTED STATES

Remedial Action
Jones Road Ground Water Plume
Houston, Harris County, Texas







11600 Jones Road

Notes:

Sampling Dates: July 30, 2019 (top) January 14, 2020 (bottom)

All results in $\mu g/m^3$ (micrograms per cubic meter)

"U" indicates the result was below the


Image Source: GoogleEarth Pro, 20






Remedial Action
Jones Road Ground Water Plume
Houston, Harris County, Texas

Figure 7
PCE and TCE Concentrations, Deep SVE System Influent





September 2020

Figure 9 PCE and TCE Concentrations, Shallow SVE System Influent 1,000,000 100,000 10,000 Contaminant Concentration (µg/m³) PCE 1,000 ■TCE 100 10 7/12/20 12/22/19 1/20/20 2/18/20 3/18/20 4/16/20 5/15/20 6/13/20 8/28/19 9/26/19 10/25/19 11/23/19


Jones Road Ground Water Plume Superfund Site Houston, Harris County, Texas

September 2020


EA Engineering, Science, and Technology, Inc., PBC

Figure 10 Contaminant Mass Removal, Shallow SVE System 80,000 20,000 ■ Monthly PCE Removed (g) 18,000 ■ Monthly TCE Removed (g) 70,000 Cum. PCE Removed (g) 16,000 Cum. TCE Removed (g) 60,000 14,000 Monthly Contaminant Mass Removed (g) Cumulative Contaminant Mass Removed (g) 50,000 12,000 40,000 10,000 8,000 30,000 6,000 20,000 4,000 10,000 2,000 1/20 3/20 7/20 9/19 10/19 11/19 12/19 2/20 4/20 5/20 6/20

September 2020







September 2020

Figure 13 Water Treatment System Analytical Sampling Results 500 450 400 350 300 Concentration, µg/L ■PCE Pre-GAC 250 ■PCE Post-GAC PCE Tank ■TCE Pre-GAC 200 TCE Post-GAC TCE Tank 150 100 50 10/2/19 11/1/19 12/1/19 12/31/19 1/30/20 2/29/20 3/30/20 4/29/20 5/29/20 7/28/20 8/27/20 8/3/19 6/28/20 7/4/19 9/2/19

EA Engineering, Science, and Technology, Inc., PBC

September 2020






Table 1 SVE System Readings

| | | SVE De | eep System | SVE Shallow System | | | | | |
|---------------------|--------------|------------|-------------|--------------------|------------|--------------|-------------------|----------------|------------------|
| | Blower | | Effluent | | LRP In | | Effluent Effluent | | |
| | Vacuum Flow | | Temperature | Blower | Vacuum | Flow | Temperature | LRP | MS Total |
| Data | (in. WC) | (scfm) | (°F) | Hours | (in. Hg) | (scfm) | (°F) | Hours | |
| Date 7/29/19 | (III. WC) | (SCIIII) | () | Hours | (III. 11g) | (SCIIII) | , | Hours | Flow (Gal) |
| | - | - | - | - | - | - | - | - | - |
| 8/2/19 | - | 269 | 1(5 | 273 | - | - | - | 1/1 | - |
| 8/6/19 8/13/19 | 51.1 39.7 | 268 | 165 | 395 | - | - | - | 161 | - |
| 8/13/19 | 41.4 | 305 306 | 166 153 | 562 | - | - | - | 161 161 | - |
| 8/23/19 | 41.4 | 305 | 149 | 634 | 26.7 | 15.8 | 120 | 189 | - |
| 8/30/19 | 44.2 | 291 | 154 | 809 | - | | | 258 | |
| 9/6/19 | 45.2 | 293 | 152 | 989 | - | - | - | 261 | - |
| 9/13/19 | 48.8 | 284 | 170 | 1,164 | | <u>-</u> | | 261 | - |
| 9/20/19 | 50.9 | 281 | 156 | 1,332 | 25.2 | 33.4 | 124 | 306 | - |
| 9/27/19 | 49.6 | 275 | 159 | 1,499 | - | | - | 306 | _ |
| 10/4/19 | 50.8 | 274 | 162 | 1,667 | _ | <u> </u> | | 310 | _ |
| 10/11/19 | 56.1 | 276 | 139 | 1,834 | 24.6 | 40.5 | 126 | 373 | 1,375 |
| 10/18/19 | 51.3 | 274 | 147 | 2,002 | 22.4 | 62.5 | 124 | 520 | 1,425 |
| 10/25/19 | 55.7 | 275 | 136 | 2,170 | 25.1 | 35.4 | 119 | 601 | 1,645 |
| 10/30/19 | 57.3 | 271 | 135 | 2,289 | 25.0 | 36.2 | 121 | 716 | 1,725 |
| 11/7/19 | 56.9 | 269 | 145 | 1,775 | 25.3 | 35.1 | 121 | 314 | 1,875 |
| 11/15/19 | 57.8 | 274 | 137 | 1,942 | 25.7 | 30.2 | 116 | 460 | 1,985 |
| 11/23/19 | 59.3 | 263 | 142 | 2,110 | 25.3 | 34.2 | 118 | 541 | 2,035 |
| 11/25/19 | 54.7 | 274 | 149 | 2,277 | 25.0 | 37.0 | 123 | 704 | 2,055 |
| 12/2/19 | 64.3 | 258 | 148 | 2,445 | 25.6 | 30.9 | 117 | 872 | 2,275 |
| 12/9/19 | 56.2 | 263 | 155 | 2,604 | 25.0 | 36.9 | 124 | 1,007 | 2,545 |
| 12/16/19 | 60.0 | 256 | 144 | 2,771 | 25.7 | 30.0 | 120 | 1,114 | 3,545 |
| 12/23/19 | 64.8 | 239 | 151 | 2,939 | 23.5 | 53.8 | 123 | 1,252 | 4,385 |
| 12/30/19 | 66.8 | 248 | 144 | 3,107 | 25.6 | 32.2 | 116 | 1,407 | 4,855 |
| 1/6/20 | 64.3 | 232 | 158 | 3,274 | 25.4 | 34.5 | 122 | 1,572 | 5,535 |
| 1/13/20 | 66.0 | 227 | 163 | 3,442 | - | - | 1 | 1,734 | 5,955 |
| 1/20/20 | 41.5 | 319 | 123 | 3,609 | 24.1 | 44.2 | 104 | 1,899 | 6,355 |
| 1/27/20 | - | - | - | 3,777 | - | - | - | 2,062 | 6,815 |
| 2/3/20 | 41.5 | 335 | 104 | 3,945 | 23.1 | 54.5 | 99 | 2,226 | 6,845 |
| 2/12/20 | 44.7 | 328 | 111 | 4,111 | 23.4 | 52.8 | 101 | 2,334 | 7,065 |
| 2/21/20 | 44.8 | 321 | 115 | 4,254 | 23.4 | 53.3 | 103 | 2,477 | 7,135 |
| 2/26/20 | | 324 | 101 | 4,324 | 23.5 | 54.2 | 98 | 2,547 | 7,635 |
| 3/4/20 | 43.9 | 314 | 122 | 4,442 | 23.3 | 53.9 | 106 | 2,665 | 7,655 |
| 3/11/20 | 43.1 | 320 | 136 | 4,610 | 23.2 | 55.4 | 111 | 2,833 | 7,655 |
| 3/18/20 | 42.4 | 306 | 140 | 4,778 | 25.7 | 31.7 | 104 | 3,001 | 7,675 |
| 3/25/20 | 42.0 | 308 | 146 | 4,946 | 23.4 | 53.1 | 114 | 3,168 | 9,205 |
| 4/1/20 | 43.6 | 317 | 131 | 5,113 | 23.3 | 53.4 | 109 | 3,336 | 9,205 |
| 4/8/20 | 42.3 | 304 | 145 | 5,281 | 24.2 | 44.5 | 111 | 3,504 | 10,125 |
| 4/15/20 | 43.9 | 299 | 137 | 5,449 | 24.2 | 44.8 | 110 | 3,672 | 10,675 |
| 4/22/20 | 42.1 | 302 | 150 | 5,627 | 24.4 | 42.2 | - 110 | 3,850 | 10,705 |
| 4/30/20 5/5/20 | 43.3 42.4 | 310 303 | 149 158 | 5,795 5,962 | 24.4 | 42.3 | 118 133 | 4,017 4,185 | 11,295 12,075 |
| 5/12/20 | | 303 | | , | 24.0 | 46.5 37.6 | 133 | | 12,075 |
| 5/20/20 | 42.1 | 303 | 149 | 6,111 6,248 | 24.9 | 37.0 | 128 | 4,305 4,305 | 16,285 |
| 5/27/20 | 42.7 | 302 | 150 | 6,393 | 25.1 | 33.7 | 126 | 4,303 | 18,005 |
| 6/3/20 | | 304 | 130 | 6,561 | 26.6 | 19.6 | 120 | 4,413 | 19,215 |
| 0/3/20 | 44.3 | 304 | 141 | 0,301 | 20.0 | 19.0 | 120 | 4,383 | 19,213 |

Table 1 SVE System Readings

| | SVE Deep System | | | | SVE Shallow System | | | | |
|---------|-----------------|--------|-------------|--------|--------------------|--------|-------------|-------|------------|
| | Blower Influent | | Effluent | | LRP Influent | | Effluent | | |
| | Vacuum | Flow | Temperature | Blower | Vacuum | Flow | Temperature | LRP | MS Total |
| Date | (in. WC) | (scfm) | (°F) | Hours | (in. Hg) | (scfm) | (°F) | Hours | Flow (Gal) |
| 6/10/20 | 41.7 | 306 | 163 | 6,727 | 24.5 | 38.4 | 130 | 4,749 | 19,545 |
| 6/18/20 | 44.4 | 308 | 145 | 6,865 | - | - | - | 4,887 | 18,935 |
| 6/25/20 | 33.2 | 336 | 136 | 7,033 | - | - | - | 5,055 | 19,545 |
| 7/2/20 | 32.7 | 336 | 143 | 7,193 | - | - | - | 5,215 | 19,545 |
| 7/9/20 | 32.9 | 334 | 143 | 7,278 | - | - | - | 5,300 | 19,545 |
| 7/16/20 | 33.7 | 331 | 143 | 7,372 | 23.2 | 53.6 | 129 | 5,394 | 19,935 |
| 7/22/20 | 34.1 | 336 | 139 | 7,540 | 25.2 | 32.6 | 122 | 5,420 | 26,465 |
| 7/29/20 | = | - | - | 7,707 | - | - | - | 5,420 | 26,465 |
| 7/31/20 | - | - | - | 7,980 | 26.9 | 16.2 | 119 | 6,640 | 26,465 |
| Minimum | 32.7 | 227 | 101 | N/A | 22.4 | 15.8 | 98 | N/A | N/A |
| Average | 47.8 | 294 | 144 | N/A | 24.6 | 40.4 | 117 | N/A | N/A |
| Maximum | 66.8 | 336 | 170 | N/A | 26.9 | 62.5 | 133 | N/A | N/A |

NOTES:

Dashes (-) indicate the treatment system was not operating at the time of the reading

Shaded cells indicate an instrument recording error

°F = Degrees Fahrenheit.

in. Hg = inches of mercury

in. WC = inches of water column

GAC = granular activated carbon.

Gal = gallon(s).

MS = moisture separator

scfm = standard cubic feet per minute

SVE = Soil Vapor Extraction

Table 2 **Deep SVE System Analytical Sampling Results**

| | | | | <u>*</u> | sampling Re | | T |
|----------|-------------|--------|-------|----------|-------------|-----|-----|
| | Sample Date | | TCE | 1,1-DCE | cis-1,2-DCE | | |
| Pre-GAC | 7/30/2019 | 61,000 | 2,300 | | | 20 | 52 |
| Pre-GAC | 8/7/2019 | 97,000 | 3,200 | | 2,900 | 41 | 300 |
| Pre-GAC | 8/28/2019 | 31,000 | 1,050 | | 810 | 9 | 22 |
| Pre-GAC | 9/18/2019 | 35,000 | 1,200 | | 890 | 12 | 15 |
| Pre-GAC | 10/10/2019 | 27,000 | | BRL | | BRL | BRL |
| Pre-GAC | 10/24/2019 | 28,000 | 940 | | 780 | 8 | 14 |
| Pre-GAC | 12/4/2019 | 17,000 | | BRL | | BRL | BRL |
| Pre-GAC | 12/16/2019 | 1,400 | | BRL | BRL | BRL | BRL |
| Pre-GAC | 12/30/2019 | 8,800 | 380 | | | BRL | BRL |
| Pre-GAC | 1/14/2020 | 11,000 | 510 | | | BRL | BRL |
| Pre-GAC | 2/12/2020 | 2,900 | | BRL | | BRL | BRL |
| Pre-GAC | 3/18/2020 | 2,000 | | BRL | | BRL | BRL |
| Pre-GAC | 4/30/2020 | 1,300 | | BRL | | BRL | BRL |
| Pre-GAC | 5/20/2020 | 525 | | BRL | | BRL | BRL |
| Pre-GAC | 6/24/2020 | 190 | | BRL | | BRL | BRL |
| Pre-GAC | 7/22/2020 | | BRL | BRL | BRL | BRL | BRL |
| Mid-GAC | 7/30/2019 | | BRL | BRL | BRL | BRL | 42 |
| Mid-GAC | 8/7/2019 | | BRL | | BRL | BRL | 320 |
| Mid-GAC | | BRL | BRL | 9 | 1,500 | 19 | 13 |
| Mid-GAC | 9/18/2019 | BRL | 14 | | 790 | 8 | 14 |
| Mid-GAC | 10/10/2019 | 23,500 | 1,950 | | | 10 | |
| Mid-GAC | 10/24/2019 | 20,000 | | | | 8 | |
| Mid-GAC | 12/4/2019 | | BRL | BRL | BRL | BRL | BRL |
| Mid-GAC | 12/16/2019 | BRL | BRL | BRL | BRL | BRL | BRL |
| Mid-GAC | 12/30/2019 | BRL | BRL | 6 | | BRL | 5 |
| Mid-GAC | 1/14/2020 | 220 | 10 | | 520 | | BRL |
| Mid-GAC | 2/12/2020 | | BRL | BRL | | BRL | BRL |
| Mid-GAC | 3/18/2020 | | BRL | BRL | | BRL | BRL |
| Mid-GAC | 4/30/2020 | | BRL | BRL | BRL | BRL | BRL |
| Mid-GAC | 5/20/2020 | | BRL | BRL | BRL | BRL | BRL |
| Mid-GAC | 6/24/20 | | BRL | BRL | | BRL | BRL |
| Mid-GAC | 7/22/20 | BRL | BRL | BRL | | BRL | BRL |
| Post-GAC | 7/30/19 | | BRL | BRL | BRL | BRL | 44 |
| Post-GAC | 8/7/19 | | BRL | BRL | BRL | BRL | 90 |
| Post-GAC | 8/28/19 | | BRL | | BRL | BRL | 13 |
| Post-GAC | 9/18/19 | BRL | BRL | 7 | 900 | 14 | 13 |
| Post-GAC | 10/10/19 | | BRL | BRL | 1,700 | | 16 |
| Post-GAC | 10/24/19 | | BRL | BRL | | BRL | 6 |
| Post-GAC | | BRL | BRL | BRL | | | BRL |
| Post-GAC | 12/16/19 | | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 12/30/19 | | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 1/14/20 | | BRL | BRL | BRL | BRL | , / |
| Post-GAC | 2/12/20 | | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 3/18/20 | | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 4/30/20 | | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 5/20/20 | | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 6/24/20 | BRL | BRL | BRL | BRL | BRL | BRL |
| Post-GAC | 7/22/20 | BRL | BRL | BRL | BRL | BRL | BRL |
| NOTES: | | | | | | | |

Concentrations are reported in micrograms per cubic meter (µg/m³). BRL = Below Reporting Limit

DCE = Dichloroethene.

GAC = Granular Activated Carbon.

PCE = Tetrachloroethene. TCE = Trichloroethene.

Table 3
Deep SVE System Analytical Sampling Results Summary

| | PC | E Concentra | ition | TC | E Concentra | ntion |
|----------|---------|-------------|----------|---------|-------------|----------|
| Date | Pre-GAC | Mid-GAC | Post-GAC | Pre-GAC | Mid-GAC | Post-GAC |
| 7/30/19 | 61,000 | 25 | 7 | 2,300 | BRL | BRL |
| 8/7/19 | 97,000 | 3 | 2 | 3,200 | BRL | BRL |
| 8/28/19 | 31,000 | BRL | 4 | 1,050 | BRL | BRL |
| 9/18/19 | 35,000 | BRL | BRL | 1,200 | 14 | BRL |
| 10/10/19 | 27,000 | 23,500 | 41 | 870 | 1,950 | BRL |
| 10/24/19 | 28,000 | 20,000 | 27 | 940 | 980 | BRL |
| 12/4/19 | 17,000 | BRL | BRL | 520 | BRL | BRL |
| 12/16/19 | 1,400 | BRL | BRL | 20 | BRL | BRL |
| 12/30/19 | 8,800 | BRL | BRL | 380 | BRL | BRL |
| 1/14/20 | 11,000 | 220 | 120 | 510 | 10 | BRL |
| 2/12/20 | 2,900 | 160 | 110 | 120 | BRL | BRL |
| 3/18/20 | 2,000 | 210 | 160 | 92 | BRL | BRL |
| 4/30/20 | 1,300 | 170 | 130 | 52 | BRL | BRL |
| 5/20/20 | 525 | BRL | BRL | 27 | BRL | BRL |
| 6/24/20 | 190 | BRL | BRL | 10 | BRL | BRL |
| 7/22/20 | 6 | BRL | BRL | BRL | BRL | BRL |

Concentrations are reported in micrograms per cubic meter (μ g/m³).

BRL = Below Reporting Limit

GAC = Granular Activated Carbon.

PCE = Tetrachloroethene.

Table 4
Deep SVE System Uptime and Mass Removal Summary

| | | | | | Volume of | | | Monthly | Cum. | PCE | | Monthly | | TCE |
|-------|------|--------|--------|--------|-----------|---------------|--------------|---------|---------|-----------|---------------|---------|----------|-----------|
| | | | | Avg. | Air | | PCE | PCE | PCE | Removal | TCE | TCE | Cum. TCE | Removal |
| | | Uptime | Uptime | Flow | Extracted | Sample | Conc. | Removed | Removed | Rate | Conc. | Removed | Removed | Rate |
| Month | Days | (days) | (%) | (SCFM) | (m^3) | Date(s)* | $(\mu g/m3)$ | (g) | (g) | (lb./hr.) | $(\mu g/m^3)$ | (g) | (g) | (lb./hr.) |
| 8/19 | 28 | 26 | 93% | 290 | 307,500 | 7/30,8/7,8/28 | 62,667 | 19,267 | 19,267 | 0.06807 | 2,167 | 666 | 666 | 0.00235 |
| 9/19 | 28 | 28 | 100% | 250 | 285,400 | 9/18 | 35,000 | 9,990 | 29,257 | 0.03277 | 1,200 | 343 | 1,009 | 0.00112 |
| 10/19 | 35 | 35 | 100% | 280 | 399,600 | 10/10 | 27,000 | 10,789 | 40,047 | 0.02832 | 870 | 348 | 1,356 | 0.00091 |
| 11/19 | 28 | 27.5 | 98% | 280 | 302,800 | 10/24 | 28,000 | 8,477 | 48,524 | 0.02832 | 940 | 285 | 1,641 | 0.00095 |
| 12/19 | 35 | 32 | 91% | 250 | 326,200 | 12/4,12/16 | 9,200 | 3,001 | 51,525 | 0.00862 | 270 | 88 | 1,729 | 0.00025 |
| 1/20 | 28 | 24.8 | 89% | 240 | 242,700 | 12/30,1/14 | 59,400 | 14,416 | 65,941 | 0.05340 | 445 | 108 | 1,837 | 0.00040 |
| 2/20 | 28 | 28 | 100% | 325 | 371,100 | 2/12 | 2,900 | 1,076 | 67,018 | 0.00353 | 120 | 45 | 1,882 | 0.00015 |
| 3/20 | 28 | 28 | 100% | 320 | 365,400 | 3/19 | 2,000 | 731 | 67,748 | 0.00240 | 92 | 34 | 1,915 | 0.00011 |
| 4/20 | 35 | 27.5 | 79% | 310 | 353,900 | 4/30 | 1,300 | 460 | 68,208 | 0.00154 | 52 | 18 | 1,934 | 0.00006 |
| 5/20 | 28 | 26 | 93% | 305 | 323,400 | 5/20 | 525 | 170 | 68,378 | 0.00060 | 27 | 9 | 1,942 | 0.00003 |
| 6/20 | 28 | 21 | 75% | 305 | 261,200 | 6/24 | 190 | 50 | 68,428 | 0.00022 | 10 | 3 | 1,945 | 0.00001 |
| 7/20 | 35 | 21.4 | 61% | 333 | 290,600 | 7/22 | 6 | 2 | 68,429 | 0.00001 | 0 | 0 | 1,945 | 0.00000 |

*Sample Date is the sample collection date that PCE and TCE concentrations (Table 3) were used to extrapolate mass removal calculations. If multiple dates are listed, the arithmetic average of concentrations from those samples was used.

 $\mu g = micrograms$

conc. = concentration

cum. = cumulative

g = grams

hr. = hour

lb. = pound

 m^3 = cubic meters

PCE = Tetrachloroethene.

SCFM = Standard cubic feet per minute

Table 5
Deep SVE Well Analytical Sampling Results

| Date | Contaminant | SVE-1 | SVE-2 | SVE-3 | SVE-4 | SVE-5 | SVE-6 | SVE-7 | SVE-9 | SVE-10 | SVE-11 |
|----------|-------------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| 7/30/19 | | 52,000 | 65,000 | 12,000 | 51,000 | 11,000 | 27,500 | 11,000 | 23,000 | 8,500 | 4,900 |
| 1/14/20 | PCE | 45,000 | 44,000 | 4,300 | 240 | 4,200 | 760 | 400 | 11,000 | 150 | 320 |
| Decrease | | 13% | 32% | 64% | 100% | 62% | 97% | 96% | 52% | 98% | 93% |
| 7/30/19 | | 1,400 | 2,500 | 170 | 1,900 | 340 | 815 | 320 | 1,100 | 390 | 230 |
| 1/14/20 | TCE | 1,200 | 2,800 | 97 | J 12 | 310 | 34 | 28 | 840 | J 10 | J 18 |
| Decrease | | 14% | -12% | 43% | 99% | 9% | 96% | 91% | 24% | 97% | 92% |

Concentrations are reported in micrograms per cubic meter (µg/m³).

J = Analysis result is estimated

PCE = Tetrachloroethene

SVE = Soil vapor extraction.

September 2020

Table 6 Shallow SVE System Analytical Sampling Results

| G I ID | G 1 D / | | SVE System | | | | 17' 1Cll '1 |
|-----------|-------------|-----------|------------|-----------|-----------|---------------|--|
| Sample ID | Sample Date | PCE | TCE | 1,1-DCE | | trans-1,2 DCE | Vinyl Chloride |
| Pre-GAC | 7/30/2019 | Cancelled | Cancelled | Cancelled | Cancelled | Cancelled | Cancelled |
| Pre-GAC | 8/28/2019 | 730,000 | 43,000 | | 55,000 | 1,200 | · · |
| Pre-GAC | 9/18/2019 | 38,000 | | | 42,000 | 1,350 | · · |
| Pre-GAC | 10/10/2019 | 970,000 | | | 86,000 | · | |
| Pre-GAC | 10/24/2019 | 160,000 | · | | 7,300 | 240 | 1,600 |
| Pre-GAC | 12/4/2019 | 180,000 | 6,700 | | 9,700 | 210 | 1,600 |
| Pre-GAC | 12/16/2019 | 200,000 | 8,800 | 27 | 18,000 | 190 | 2,000 |
| Pre-GAC | 12/30/2019 | 320,000 | 13,500 | 46 | 24,500 | 230 | 2,100 |
| Pre-GAC | 1/14/2020 | 235,000 | 28,500 | 27 | 21,000 | 195 | 670 |
| Pre-GAC | 2/12/2020 | 42,000 | 1,500 | 8 | 2,500 | 49 | 490 |
| Pre-GAC | 3/19/2020 | 120,000 | 5,700 | 21 | 12,000 | 110 | 980 |
| Pre-GAC | 4/30/2020 | 21,000 | 640 | 3 | 1,200 | 23 | 240 |
| Pre-GAC | 5/20/2020 | 90,000 | 3,800 | 17 | 7,600 | 82 | 800 |
| Pre-GAC | 6/24/2020 | 130,000 | 3,000 | 10 | 6,200 | 58 | 510 |
| Pre-GAC | 7/22/2020 | 330,000 | 10,000 | 35 | 18,000 | 130 | 1,300 |
| Mid-GAC | 7/30/2019 | 130 | BRL | BRL | BRL | BRL | 5,400 |
| Mid-GAC | 8/28/2019 | BRL | 1,700 | 160 | 42,000 | 490 | 14,000 |
| Mid-GAC | 9/18/2019 | 21 | 690 | 19 | 14,000 | 140 | 4,000 |
| Mid-GAC | 10/10/2019 | 15,000 | 24,000 | 250 | 85,000 | 1,600 | 16,000 |
| Mid-GAC | 10/24/2019 | 81,000 | 7,200 | 30 | 7,300 | 180 | 2,000 |
| Mid-GAC | 12/4/2019 | 180 | 12 | BRL | 100 | BRL | 1,800 |
| Mid-GAC | 12/16/2019 | 95 | 26 | BRL | 150 | BRL | BRL |
| Mid-GAC | 12/30/2019 | 19,000 | 3,500 | 36 | 11,000 | 140 | 2,000 |
| Mid-GAC | 1/14/2020 | 120,000 | 3,800 | BRL | 6,000 | BRL | 290 |
| Mid-GAC | 2/12/2020 | 6,200 | 820 | 20 | 3,900 | 48 | 480 |
| Mid-GAC | 3/18/2020 | 76,000 | 21,000 | 33 | 30,000 | 340 | 1,200 |
| Mid-GAC | 4/30/2020 | 510 | BRL | BRL | BRL | BRL | 47 |
| Mid-GAC | 5/20/2020 | 1,100 | 510 | 40 | 8,000 | 74 | 610 |
| Mid-GAC | 6/24/2020 | 47,000 | 1,800 | 6 | 3,300 | 32 | 320 |
| Mid-GAC | 7/22/2020 | 110,000 | 10,000 | 39 | 31,000 | 240 | 1,600 |
| Post-GAC | 7/30/2019 | BRL | BRL | BRL | BRL | BRL | 5,100 |
| Post-GAC | 8/28/2019 | BRL | BRL | BRL | BRL | BRL | 11,000 |
| Post-GAC | 9/18/2019 | BRL | BRL | 10 | 7 | BRL | 1,200 |
| Post-GAC | 10/10/2019 | BRL | BRL | 120 | 670 | BRL | 18,000 |
| Post-GAC | 10/24/2019 | 2,100 | 2,000 | 47 | 21,000 | 360 | 2,000 |
| Post-GAC | 12/4/2019 | | BRL | BRL | | BRL | 2,200 |
| Post-GAC | 12/16/2019 | 29 | 17 | | 1,200 | | · · |
| Post-GAC | 12/30/2019 | 130 | | | 6,700 | 100 | |
| Post-GAC | 1/14/2020 | 8,900 | | | 27,000 | | , and the second |
| Post-GAC | 2/12/2020 | 4,000 | - | | | | |
| Post-GAC | 3/18/2020 | 3,700 | | | | | |

EA Project No.: 14342.129

Revision: 00 Table 6, Page 2 of 2 September 2020

EA Engineering, Science, and Technology, Inc., PBC

Table 6 Shallow SVE System Analytical Sampling Results

| Sample ID | Sample Date | PCE | TCE | 1,1-DCE | cis-1,2-DCE | trans-1,2 DCE | Vinyl Chloride |
|-----------|-------------|--------|-------|----------------|-------------|---------------|----------------|
| Post-GAC | 4/30/2020 | 230 | 9 | BRL | 11 | BRL | BRL |
| Post-GAC | 5/20/2020 | 97 | 41 | 29 | 700 | 13 | 690 |
| Post-GAC | 6/24/2020 | 2,900 | 600 | 11 | 5,700 | 45 | 460 |
| Post-GAC | 7/22/2020 | 39,000 | 4,800 | 37 | 18,000 | 170 | 1,500 |
| | | | | | | | |

NOTES:

Concentrations are reported in micrograms per cubic meter ($\mu g/m^3$).

BRL = Below Reporting Limit

DCE = Dichloroethene.

GAC = Granular Activated Carbon.

PCE = Tetrachloroethene.

Table 7
Shallow SVE System Analytical Sampling Summary

| Data | PC | E Concentra | ition | TC | E Concentra | tion |
|----------|-----------|-------------|----------|-----------|-------------|----------|
| Date | Pre-GAC | Mid-GAC | Post-GAC | Pre-GAC | Mid-GAC | Post-GAC |
| 7/30/19 | Cancelled | 130 | BRL | Cancelled | BRL | BRL |
| 8/28/19 | 730,000 | BRL | BRL | 43,000 | 1,700 | BRL |
| 9/18/19 | 38,000 | 21 | BRL | 15,000 | 690 | BRL |
| 10/10/19 | 970,000 | 15,000 | BRL | 50,000 | 24,000 | BRL |
| 10/24/19 | 160,000 | 81,000 | 2,100 | 7,300 | 7,200 | 2,000 |
| 12/4/19 | 180,000 | 180 | 160 | 6,700 | 12 | BRL |
| 12/16/19 | 200,000 | 95 | 29 | 8,800 | 26 | 17 |
| 12/30/19 | 320,000 | 19,000 | 130 | 13,500 | 3,500 | 220 |
| 1/14/20 | 235,000 | 120,000 | 8,900 | 28,500 | 3,800 | 5,400 |
| 2/12/20 | 42,000 | 6,200 | 4,000 | 1,500 | 820 | 1,200 |
| 3/19/20 | 120,000 | 76,000 | 3,700 | 5,700 | 21,000 | 1,300 |
| 4/30/20 | 21,000 | 510 | 230 | 640 | 6 | 9 |
| 5/20/20 | 90,000 | 1,100 | 97 | 3,800 | 510 | 41 |
| 6/24/20 | 130,000 | 47,000 | 2,900 | 3,000 | 1,800 | 600 |
| 7/22/20 | 330,000 | 110,000 | 39,000 | 10,000 | 10,000 | 4,800 |

Concentrations are reported in micrograms per cubic meter (µg/m³).

BRL = Below Reporting Limit

GAC = Granular Activated Carbon.

PCE = Tetrachloroethene.

Table 8
Shallow SVE System Uptime and Mass Removal Summary

| | | | | | Volume of | | | Monthly | | PCE | | Monthly | | TCE |
|-------|------|--------|--------|--------|-----------|------------|---------|---------|----------|-----------|---------------|---------|----------|-----------|
| | | | | Avg. | Air | | PCE | PCE | Cum. PCE | Removal | TCE | TCE | Cum. TCE | Removal |
| | | Uptime | Uptime | Flow | Extracted | Sample | Conc. | Removed | Removed | Rate | Conc. | Removed | Removed | Rate |
| Month | Days | (days) | (%) | (SCFM) | (m^3) | Date(s)* | (μg/m3) | (g) | (g) | (lb./hr.) | $(\mu g/m^3)$ | (g) | (g) | (lb./hr.) |
| 8/19 | 28 | 5 | 18% | 11 | 2,243 | 8/28 | 730,000 | 1,637 | 1,637 | 0.0301 | 43,000 | 96 | 96 | 0.0018 |
| 9/19 | 28 | 2 | 7% | 14 | 1,142 | 9/18 | 38,000 | 44 | 1,681 | 0.0020 | 15,500 | 18 | 115 | 0.0008 |
| 10/19 | 35 | 18 | 51% | 20 | 14,679 | 10/10 | 970,000 | 14,076 | 15,757 | 0.0718 | 50,000 | 741 | 856 | 0.0038 |
| 11/19 | 28 | 23 | 82% | 20 | 29,073 | 10/24 | 160,000 | 4,779 | 20,536 | 0.0191 | 7,300 | 221 | 1,077 | 0.0009 |
| 12/19 | 35 | 31.0 | 89% | 35 | 44,311 | 12/4,12/16 | 190,000 | 8,650 | 29,186 | 0.0256 | 7,750 | 337 | 1,413 | 0.0010 |
| 1/20 | 28 | 22 | 79% | 38 | 34,089 | 12/30,1/14 | 277,500 | 9,690 | 38,875 | 0.0405 | 21,000 | 731 | 2,144 | 0.0031 |
| 2/20 | 28 | 28 | 100% | 55 | 62,795 | 2/12 | 42,000 | 2,637 | 41,513 | 0.0087 | 1,500 | 94 | 2,239 | 0.0003 |
| 3/20 | 28 | 28 | 100% | 30 | 34,252 | 3/19 | 120,000 | 4,110 | 45,623 | 0.0135 | 5,700 | 195 | 2,434 | 0.0006 |
| 4/20 | 35 | 35 | 100% | 50 | 59,125 | 4/30 | 21,000 | 1,242 | 46,865 | 0.0033 | 640 | 38 | 2,472 | 0.0001 |
| 5/20 | 28 | 26 | 93% | 38 | 40,287 | 5/20 | 90,000 | 3,626 | 50,491 | 0.0128 | 3,800 | 153 | 2,625 | 0.0005 |
| 6/20 | 28 | 18.5 | 66% | 36 | 27,157 | 6/24 | 130,000 | 3,530 | 54,021 | 0.0175 | 3,000 | 81 | 2,706 | 0.0004 |
| 7/20 | 35 | 18.8 | 54% | 33 | 24,953 | 7/22 | 330,000 | 8,234 | 62,255 | 0.0402 | 10,000 | 250 | 2,956 | 0.0012 |

*Sample Date is the sample collection date that was used to extrapolate mass removal calculations. If multiple dates are listed, the arithmetic average of concentrations from those samples was used.

 $\mu g = micrograms$

conc. = concentration

cum. = cumulative

g = grams

hr. = hour

lb. = pound

 m^3 = cubic meters

PCE = Tetrachloroethene.

SCFM = Standard cubic feet per minute

Revision: 00

Table 9, Page 1 of 1

September 2020

EA Engineering, Science, and Technology, Inc., PBC

Table 9 Shallow SVE Well Analytical Sampling Results

| Date | Contaminant | SSVE-4 | SSVE-5 | SSVE-6 | SSVE-7 | SSVE-8 | SSVE-9 | SSVE-10 | SSVE-11 | SSVE-12 | SSVE-13 | SSVE-14 |
|----------|-------------|---------|-----------|--------|-----------|--------|--------|-----------|---------|---------|---------|---------|
| 7/30/19 | | 200,000 | 1,700,000 | 160 | 2,100,000 | 7,100 | 56,000 | 17,000 | 130,000 | 9,200 | 10,000 | 5,100 |
| 1/14/20 | PCE | 360,000 | 34,000 | 1,100 | 1,000,000 | 1,500 | 46,000 | 1,200,000 | 64,000 | 7,700 | 16,000 | 1,200 |
| Decrease | | -80% | 98% | -588% | 52% | 79% | 18% | -6959% | 51% | 16% | -60% | 76% |
| 7/30/19 | | 6,100 | 9,600 | U 8 | 120,000 | 310 | 4,700 | 640 | 19,000 | 1,200 | 300 | 290 |
| 1/14/20 | TCE | 2,700 | 410 | 58 | 34,000 | 140 | 2,800 | 120,000 | 17,000 | 430 | 4,200 | 39 |
| Decrease | | 56% | 96% | -625% | 72% | 55% | 40% | -18650% | 11% | 64% | -1300% | 87% |

NOTES:

Concentrations are reported in micrograms per cubic meter ($\mu g/m^3$).

U = Analysis result below the method detection limit

PCE = Tetrachloroethene

SVE = Soil vapor extraction.

EA Project No.: 14342.129

Revision: 00 Table 10, Page 1 of 1 September 2020

EA Engineering, Science, and Technology, Inc., PBC

Table 10
Deep SVE System Photoionization Detector Readings

| | Treat | tment S | ystem | | | | | Wel | lheads | | | | |
|---------|-------|---------|-------|------|---|------|------|------|--------|------|------|------|------|
| | Pre- | Mid- | Post- | SVE- | SVE- SVE- SVE- SVE- SVE- SVE- SVE- SVE- | | | | | | | | |
| Date | GAC | GAC | GAC | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 9 | 10 | 11 |
| 5/12/20 | 47.2 | 11.1 | 7.8 | 80.2 | 67.1 | 43.8 | 60.1 | 36.2 | 51.2 | 18.2 | 82.1 | 51.9 | 77.2 |
| 5/20/20 | 4.3 | 0.4 | 0.0 | 49.5 | 64.3 | 24.9 | 68.3 | 3.5 | 14.8 | 16.9 | 46.8 | 43.8 | 168 |
| 6/10/20 | 0.1 | 0.0 | 0.0 | 12.1 | 27.1 | 23.4 | 19 | 2.5 | 1.1 | 4.9 | 23.2 | 8.2 | 11.9 |
| 7/22/20 | 12.9 | 15.3 | 16.6 | 3.5 | 5.0 | 2.1 | 3.5 | 0.9 | 0.3 | 0.4 | 2.9 | 1.4 | 14 |

NOTES:

Reading are for total volatile organic compounds and recorded in ppmv.

GAC = Granular activated carbon.

ppmv = Parts per million by volume.

SVE = Soil vapor extraction.

EA Project No.: 14342.129

Revision: 00 Table 11, Page 1 of 1 September 2020

EA Engineering, Science, and Technology, Inc., PBC

Table 11
Shallow SVE System Photoionization Detector Readings

| | Treat | ment S | ystem | | | | | V | Vellhead | ds | | | | |
|---------|-------|--------|-------|-------|-------|-------|-------|-------|----------|-------|-------|-------|-------|-------|
| | Pre- | Mid- | | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- | SSVE- |
| Date | GAC | GAC | GAC | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | 14 |
| 5/12/20 | 70.2 | 55.6 | 75.6 | 37.5 | 54.9 | 65.4 | 62.6 | 28.6 | 12.8 | 168 | 9.4 | 6.3 | 2.2 | 24 |
| 5/20/20 | 47.1 | 17.1 | 11.0 | 32.8 | 20.2 | 81.4 | 28.1 | 15.2 | 7.8 | 3.5 | 1.4 | 19.4 | 1 | 17.9 |
| 6/10/20 | 33.5 | 23.9 | 24.2 | 1.8 | 6.2 | 10.8 | 13.7 | 12.1 | 6.7 | 4.8 | 0.8 | 21.3 | 3 | 32.8 |
| 7/22/20 | 82.8 | 143.0 | 17.7 | 27.7 | 14.2 | 28.9 | 28.8 | 2.7 | 4.7 | 6.5 | 1.3 | 4.8 | 1.8 | 2.8 |

NOTES:

Reading are for total volatile organic compounds and recorded in ppmv.

GAC = Granular activated carbon.

ppmv = Parts per million by volume.

SVE = Soil vapor extraction.

Table 12
Water Treatment System Sampling Results

| | | | catificht bys | <u> </u> | | trans-1,2 | Vinyl |
|--------------|-------------|-------|---------------|----------|-------------|-----------|----------|
| Sample ID | Sample Date | PCE | TCE | 1,1-DCE | cis-1,2-DCE | DCE | Chloride |
| Pre-GAC | 7/30/2019 | 356.5 | | BRL | | BRL | 2.3 |
| Pre-GAC | 8/1/2019 | 237.0 | 24.7 | BRL | | BRL | BRL |
| Pre-GAC | 8/27/2019 | 432.0 | | BRL | 186.0 | 2.0 | 6.7 |
| Pre-GAC | 12/16/2019 | 160.0 | 13.1 | BRL | 56.7 | BRL | BRL |
| Pre-GAC | 1/29/2020 | 46.7 | 3.2 | BRL | 12.1 | BRL | BRL |
| Pre-GAC | 3/23/2020 | 37.4 | 4.5 | BRL | 34.4 | BRL | BRL |
| Pre-GAC | 4/20/2020 | 27.2 | 1.5 | BRL | 6.4 | BRL | BRL |
| Pre-GAC | 7/22/2020 | 58.8 | 4.0 | BRL | 18.4 | BRL | BRL |
| Mid-GAC | 7/30/2019 | 237.0 | 19.9 | BRL | 59.6 | BRL | BRL |
| Mid-GAC | 8/1/2019 | 238.0 | 22.1 | BRL | 78.6 | BRL | BRL |
| Mid-GAC | 8/27/2019 | 402.0 | 48.4 | BRL | 183.0 | 1.9 | 7.1 |
| Mid-GAC | 12/16/2019 | 72.5 | 7.2 | BRL | 31.4 | BRL | BRL |
| Mid-GAC | 1/29/2020 | 61.8 | 3.6 | BRL | 12.2 | BRL | BRL |
| Mid-GAC | 4/20/2020 | 25.7 | 1.5 | BRL | 6.8 | BRL | BRL |
| Mid-GAC | 7/22/2020 | 58.8 | 4.2 | BRL | 18.4 | BRL | BRL |
| Post-GAC | 7/30/2019 | 146.0 | 16.0 | BRL | 37.8 | BRL | BRL |
| Post-GAC | 8/1/2019 | 155.5 | 14.6 | BRL | 48.4 | BRL | BRL |
| Post-GAC | 8/13/2019 | 44.6 | 3.6 | BRL | 11.6 | BRL | BRL |
| Post-GAC | 8/20/2019 | 44.4 | 3.7 | BRL | 11.3 | BRL | BRL |
| Post-GAC | 8/27/2019 | 406.5 | 47.2 | BRL | 183.0 | 1.8 | |
| Post-GAC | 12/16/2019 | 97.8 | 9.4 | BRL | | BRL | BRL |
| Post-GAC | 1/29/2020 | 42.1 | 3.4 | BRL | 11.7 | BRL | BRL |
| Post-GAC | 3/23/2020 | 65.1 | 6.8 | BRL | 47.1 | BRL | BRL |
| Post-GAC | 4/20/2020 | 25.3 | | BRL | | BRL | BRL |
| Post-GAC | 7/22/2020 | 48.9 | | BRL | | BRL | BRL |
| Storage Tank | 8/1/2019 | 119.0 | | BRL | 36.4 | BRL | BRL |
| Storage Tank | 8/7/2019 | 29.7 | | BRL | | BRL | BRL |
| Storage Tank | 8/9/2019 | 34.8 | | BRL | | BRL | BRL |
| Storage Tank | 8/13/2019 | | BRL | BRL | | BRL | BRL |
| Storage Tank | 8/20/2019 | BRL | BRL | BRL | | BRL | BRL |
| Storage Tank | 8/27/2019 | 9.9 | | BRL | | BRL | BRL |
| Storage Tank | 10/24/2019 | | BRL | BRL | BRL | BRL | BRL |
| Storage Tank | 12/16/2019 | 13.0 | 1.5 | BRL | 9.0 | BRL | BRL |
| Storage Tank | 12/30/2019 | 27.1 | | BRL | | BRL | BRL |
| Storage Tank | 1/15/2020 | 11.9 | | BRL | | BRL | BRL |
| Storage Tank | 1/29/2020 | | BRL | BRL | | BRL | BRL |
| Storage Tank | 3/23/2020 | | BRL | BRL | | BRL | BRL |
| Storage Tank | 4/20/2020 | BRL | BRL | BRL | BRL | BRL | BRL |
| Storage Tank | 7/22/2020 | 1.3 | BRL | BRL | BRL | BRL | BRL |

Concentrations are reported in micrograms per liter (µg/L).

BRL = Below Reporting Limit

DCE = Dichloroethene.

GAC = Granular Activated Carbon.

PCE = Tetrachloroethene.

Table 13
Summary of Water Treatment System Analytical Sampling

| | PCE Concentration | | | | TCE Concentration | | | |
|----------|-------------------|-------------|--------------|-------|-------------------|-------------|--------------|------|
| Date | Pre- GAC | Mid- GAC | Post- GAC | Tank | Pre- GAC | Mid- GAC | Post- GAC | Tank |
| 7/30/19 | 356.5 | 237.0 | 146.0 | N/S | 27.2 | 19.9 | 16.0 | N/S |
| 8/1/19 | 237.0 | 238.0 | 155.5 | 119.0 | 24.7 | 22.1 | 14.6 | 10.6 |
| 8/7/19 | N/S | N/S | N/S | 29.7 | N/S | N/S | N/S | 2.7 |
| 8/9/19 | N/S | N/S | N/S | 34.8 | N/S | N/S | N/S | 3.4 |
| 8/13/19 | N/S | N/S | 44.6 | 3.6 | N/S | N/S | 3.6 | BRL |
| 8/20/19 | N/S | N/S | 44.4 | BRL | N/S | N/S | 3.7 | BRL |
| 8/27/19 | 239.5 | 129.0 | 162.0 | 1.9 | 22.2 | 18.2 | 16.7 | BRL |
| 10/10/19 | 432.0 | 402.0 | 406.5 | 9.9 | 47.7 | 48.4 | 47.2 | 2.0 |
| 10/24/19 | N/S | N/S | N/S | BRL | N/S | N/S | N/S | BRL |
| 12/16/19 | 160.0 | 72.5 | 97.8 | 13.0 | 13.1 | 7.2 | 9.4 | 1.5 |
| 12/30/19 | N/S | N/S | N/S | 27.1 | N/S | N/S | N/S | 3.4 |
| 1/15/20 | N/S | N/S | N/S | 11.9 | N/S | N/S | N/S | 1.8 |
| 1/29/20 | 46.7 | 61.8 | 42.1 | 1.7 | 3.2 | 3.6 | 3.4 | BRL |
| 3/23/20 | 37.4 | | 65.1 | BRL | 4.5 | | 6.8 | BRL |
| 4/21/20 | 27.2 | 25.7 | 25.3 | BRL | 1.5 | BRL | BRL | BRL |
| 7/22/20 | 58.8 | 58.8 | 48.9 | 1.3 | 4.0 | 4.2 | 3.8 | BRL |

Concentrations are reported in micrograms per liter (μ g/L).

BRL = Below Reporting Limit

GAC = Granular Activated Carbon.

N/S = Not Sampled.

PCE = Tetrachloroethene.

Table 14
Summary of Ground Water Analytical Sampling

| | | PCE Concentration | | | | | | | |
|---------|---------|-------------------|--------|--------------------------------------|---------|--------------------------------------|--|--|--|
| Well | Zone | Jun-19 | Feb-20 | % Decrease Jun. '19 - Feb. '20 | Jun-20 | % Decrease Jun. '19 - Jun. '20 | | | |
| SVE-1 | Deep | 104.0 | 68.0 | 35% | 68.0 | 35% | | | |
| SVE-2 | Deep | 357.0 | 111.0 | 69% | 33.0 | 91% | | | |
| SVE-3 | Deep | 166.0 | 79.2 | 52% | 74.0 | 55% | | | |
| SVE-4 | Deep | 174.0 | 56.8 | 67% | 81.0 | 53% | | | |
| SVE-5 | Deep | 178.0 | 163.0 | 8% | 120.0 | 33% | | | |
| SVE-6 | Deep | 27.6 | 24.8 | 10% | 20.0 | 28% | | | |
| SVE-7 | Deep | 44.5 | 53.1 | -19% | 36.0 | 19% | | | |
| SVE-8 | Deep | 108.0 | 152.0 | -41% | 95.0 | 12% | | | |
| SVE-9 | Deep | 122.0 | 102.0 | 16% | 100.0 | 18% | | | |
| SVE-10 | Deep | N/S | 91.8 | | 48.0 | | | | |
| SVE-11 | Deep | N/S | 68.0 | | 22.0 | | | | |
| Average | Deep | 142.3 | 88.2 | 22% | 63.4 | 38% | | | |
| MW-01 | Shallow | N/S | BRL | | BRL | | | | |
| MW-02 | Shallow | N/S | 30.0 | | N/S | | | | |
| MW-03 | Shallow | N/S | 7.7 | | 2.5 | 68% | | | |
| MW-04 | Shallow | N/S | BRL | | N/S | | | | |
| MW-05 | Shallow | N/S | BRL | | BRL | | | | |
| MW-06 | Shallow | N/S | BRL | | N/S | | | | |
| MW-07 | Shallow | N/S | BRL | | BRL | | | | |
| MW-08 | Shallow | N/S | BRL | | N/S | | | | |
| MW-09 | Shallow | N/S | BRL | | BRL | | | | |
| MW-20 | Shallow | N/S | 8,600 | | 8,900 | -3% | | | |
| MW-21 | Shallow | N/S | BRL | | N/S | | | | |
| Average | Shallow | | 785 | | 1,483.8 | 32% | | | |

Concentrations are reported in micrograms per liter (µg/L).

BRL = Below Reporting Limit

N/S = Not Sampled.

PCE = Tetrachloroethene.

APPENDIX A

System Readings Datasheets

APPENDIX B

Field Logbook

APPENDIX C

Air Sampling Analytical Reports

APPENDIX D

Water Sampling Analytical Reports